





NORTH ELEVATION
1 : 50

Window fittings painted grey
and fascia to be painted grey to match

All new windows and doors to be desinged,
tested, certified
and installed to resits forced entry as
set out in the recommendations of secured by
Design



WEST ELEVATION
1 : 50



EAST ELEVATION
1 : 50

Level accesible patio paved area's to be
2400x2400, 3700x2400mm with landscaped
ramp to east side of property with opening Bi-
Fold doors to sunroom and bedroom, arrows
indicate direction

Bi-Fold doors to be painted grey to match
existing windows and fascia

Patio to be Kandla grey sandstone slabs

Engineering brick to be Baggeridge 100mm
Perf Blue class B eng K20965P



SOUTH ELEVATION
1 : 50