


PARTITION LAYOUT LEGEND:




Existing wall



Internal partiton build up to be
50 x 75mm stud frame @ 600 c/c
50mm insulation to be laid between studs
12.5mm mm plasterboard on both side



Internal washroom partiton build up to be
12.5 mm plasterboard
50 x 75mm stud frame @ 600 c/c
50mm insulation laid between studs
12.5mm moisture resistant plasterboard



PARTITION LAYOUT GROUND FLOOR
PLAN
1 : 50

Project:	
HOUSE EXTENSION	
Title:	
Proposed Partition Layout	
Drawing Number:	Revision
L(22)001	
Scale:	Date:
1 : 50 - A2	Oct 2020